BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/08/2016-17 Dated: 4-03-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 39

Name of Work:- Improvements to roads and drains at Chowdeshwari layout in ward no 02 yelahanka sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
1	Removing B.S. slab of Drain and stacking.(P No.25 / I N 5.32)	Sqm	333.60	62.71	Rueeps sixty two and paise seventy one only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)	Cum	195.12	83.01	Rueeps eighty thee and paise one only
3	Refixing stone slabs of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	266.88	76.93	Rueepsseventy six and paise ninety three only
4	Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	Sqm	66.72	2005.11	Rupeestwo thousand five and paise eleven only
5	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	333.00	158.93	Rupees one hundred fifty eight and paise ninety three only
6	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	528.12	95.50	Rupees fninety five and paise fifty only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	169.80	5045.90	Rupees five thousand forty five and paise ninety only
8	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.) Page No.18 / Item No. 4.48)	Cum	141.50	5800.00	Rupees five thousand eight hundred only
9	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift. Page No 177 Item No 22.7 SR 2016-17	Sqm	1132.00	91.25	Rupees ninety one and paise twenty five only
10	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement Item no 22.8.1 Page No 178 SR 2016-17	Rmt	194.00	116.41	Rupees one hundred sixteen and paise forty one only

P. channa Krishna
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.